



MCB 3P 15kA C-100A 4.5M

HMC390

Technical Properties

Rating current 30°C	100 A
Number of poles	3 P
Curve	C
Number of modules	4,5
Rated operational voltage Ue	415 V
Frequency	50/60 Hz
Height of installed product	90 mm
Depth of installed product	70 mm
Standard text	EN 60898-1 ; IEC 60947-2